

BIDDER INFORMATION		
NAME:		
ADDRESS:		
PHONE NUMBER:		
EMAIL ADDRESS:		
FAX NUMBER:		
AR CONTRACTING LICENSE NUMBER:		
Approximately 15,000 square yards of milling/1200 tons of asphalt		
SPECIFICATIONS	YES	NO
The contractor shall include all supplementary tools and equipment necessary for complete satisfactory and approved installation.		
Material, labor, equipment, etc... used in the installation of the asphalt overlay material shall be included in the unit price bid per ton of asphalt overlay material, and there will be no additional compensation therefore.		
Streets will be tacked at the discretion of the Public Works Director.		
Various streets in Wynne have been overlaid numerous times over the past years which has produced irregular slopes in the driving lanes. In order to remedy some of the situation, we require contractors interested in bidding city street projects to have asphalt paving machines with hydraulic screed extensions which extend up to four feet and tilt up to 10 degrees.		
Successful bidder will overlay 1.5 inches asphalt unless otherwise specified by the Public Works Director.		
Successful bidder will mill and overlay streets specified by the director at a rate of 1.5 inches.		
Project would preferably be completed before August 1, 2024.		
The City of Wynne will retain all milling and it will be hauled to a location designated by the city.		
SECTION ACHM - DETAILED SPECIFICATIONS - ASPHALTIC CONCRETE HOT MIX SURFACE COURSE		
ACHM - GENERAL		
This item shall consist of an asphaltic concrete wearing surface composed of a compacted mixture of mineral aggregate and asphalt cement mixed in a central mixing plant and placed on a completed and accepted base course in accordance with these specifications and shall conform to the dimensions, lines, grades, compacted thickness and typical cross section as directed by the Public Works Director.		
ACHM - PROJECT MIX FORMULA		
Work shall not begin nor shall any mixture be accepted until the contractor has submitted samples of the material intended for use and the Engineer has established a satisfactory project mix formula. The samples will be furnished in the quantities sufficient to establish a project mix as directed by the Engineer.		
ACHM - MATERIALS, EQUIPMENT & CONSTRUCTION METHODS		
Materials, equipment, construction methods and all other project items not covered in these specifications will be as required by the Standard Specification for Highway Construction, Arkansas State Highway Commission, Ed. 2003.		
ACHM - MEASUREMENT & PAYMENT		
ACHM SURFACE COURSE will be measured by the ton and paid for at the unit price per ton in the bid schedule. The unit price per ton shall include the cost of prime coat and there will be no additional compensation therefore.		
CONSTRUCTION REQUIREMENTS & ACCEPTANCE		
Construction requirements and acceptance shall comply with Section 407, Hot Mix Surface Course, Standard Specification for Highway Construction, Arkansas State Highway Commission, Ed. 2003.		
ASPHALT PRICE PER TON:		
MILLING PRICE PER SQUARE YARD:		
SIGNATURE OF BIDDER:		